

Subdivisions, T. 2 N., R. 33 E.

Chains	
40.25	Gulch N.
41.50	Wagon road N.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.
80.00	Corner to secs. 8, 9, 16 and 17. Land, slightly rolling. Soil, 2nd rate. Some alkali. Fair agricultural land.
<hr/> North between secs. 8 and 9.	
Variation 21° East.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on W. face.
24.50	Wagon road to Agency N.E.
35.00	Wagon road to Agency N.E.
40.00	Deposited charred stake 12 ins. in the ground for ¼ Sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake, 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S on W. face.
55.00	O.R. & N. Railway E & W.
77.70	Umatilla river 100 lks. wide runs W.
80.00	Set basalt stone 16 x 10 x 8 ins., 10 ins. in the ground for corner to secs. 4, 5, 8 and 9, marked with 5 notches on S and 4 notches on East edges and raised mound of stone over it.

-50