

Chains	
76.55	<p>base over it. In E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. Intersect W. bdy. Township 68 links N of corner to secs. 25 and 26 and deposited charred stake 12 ins. in the ground for closing corner to secs. 30 and 31; dug pits 18 x 18 x 12 ins. N.E. and S. of stake 5 1/2 ft. distant; raised mound of earth 2 ft. high, 4 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked C.C. T2NR33E on E.; S30 on N and S31 on S faces with one notch on S and 5 notches on N. edges.</p> <p>Land, gently rolling.</p> <p>Soil, 2nd rate, light and sandy. Fair agricultural land.</p>
20.00	<p>North bet. secs. 29 and 30.</p> <p>Var. 21° East.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in N pit drove stake 12 ins. in the ground marked 1/16 S on W face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 square 12 ins. in the ground marked 1/16 S on W face. over it and in N pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on W face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake, 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on W face.</p>
80.00	<p>Drove charred stake 12 ins. in the ground for cor. to secs. 19, 20, 29 and 30; dug pits 18 x 18 x 12 ins. in each sec., 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in S.E. pit drove stake 2 ft.</p>