

## Subdivisions, T.2 N.,R. 33 E.

Chains	
	dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on N face.
55.85	Wagon road N.
60.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $\frac{1}{16}$ S on N face.
76.68	Intersect W. boundary Township 275 lks. N of cor. to secs. 13 and 24, T 2 N R 32 E and deposited charred stake 12 ins. in the ground for closing cor. to secs. 18 and 19; dug pits 18 x 18 x 12 ins. N.E. and S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked C.C.T2NR33 E.on E.; S18 on N and S19 on S faces with 3 notches on S and N edges.
	Land, level.
	Soil, 1st rate.
<hr/>	
	North between secs. 17 and 18.
	Variation $19^{\circ}$ East.
16.75	Fence and leave field or meadow.
20.00	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for $\frac{1}{16}$ sec. cor., marked $\frac{1}{16}$ S on W. face and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.
25.00	Top hill E and W.
40.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. N and S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S on W. face.
44.50	Gulch S.W.
53.00	Wagon road.