

Chains	
	12 ins. in the ground for closing cor. to secs. 7 and 18. Dug pits 18 x 18 x 12 ins. N.E. and S of stake 5 7/8 ft. dist.; raised mound of earth 2 ft. high, 4 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked C.C.T2 N.R. 33 E. on E., S7 on N and S18 on S faces with 4 notches on S and 2 notches on N edges.
	Land, rolling.
	Soil, 2nd rate.
	North bet. secs. 7 and 8.
	Variation 20 3/4° East.
	Enter river bottom.
	Deposited charred stake 12 ins. in the ground for 1/16 sec.
	cor.; dug pits 18 x 18 x 12 ins. N and S of stake 5 7/8 ft. dist.; raised mound of earth 1 7/8 ft. high, 3 7/8 ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on W. face.
	Wagon road N.W.
	Wagon road E and W.
	Deposited charred stake 12 ins. in the ground for 3/4 sec.
	cor.; dug pits 18 x 18 x 12 ins. N and S of stake, 5 7/8 ft. dist.; raised mound of stone and earth 1 7/8 ft. high, 3 7/8 ft. base over it and in the N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 3/8 on W face.
	O.R. & N.R.R. E and W.
	A balm 8 ins. diam. which I mark T2N S5 on N.E.; R33 E S8 on S.E.; S7 on S.W. and S6 on N.W. faces with 5 notches on S and E edges for cor. to secs. 5, 6, 7 & 8, from which
	A balm 4 ins. diam bears N 30° E. 26 lks. dist.,
	marked T. 2 N.R. 33 E. S5 B.T.
	A balm 8 ins. diam. bears S 10° E 10 lks. dist.,
	marked T2 N.R. 33 E. S8 B.T.
	A balm 24 ins. diam. bears S 45° W 90 lks. dist.,
	marked T2N R33 E S7 B.T.