

Chains	
30.00	Spring branch 2 lks. course N.
39.88	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. corner; dug pits 18 x 18 x 12 ins. E and W of stake, 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on N. face. Wagon road to La Grande S.E.
48.00	Deposited charred stake 12 ins. in the ground for 1/16
59.82	sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.
79.75	$\frac{1}{4}$ sec. cor. between secs. 25 and 26. Land, rolling. Soil, 2nd rate. Very little grass.
79.88	East on random through N $\frac{1}{2}$ of Sec. 25. Variation 19° East. Commencing at 1/16 sec. cor. 20 chains N. of $\frac{1}{4}$ sec. cor. between secs. 25 and 26. Set temporary 1/16 sec. corners at 20, 40 and 60 chains and at Intersect E. boundary Township 8 links S of 1/16 sec. corner between secs. 25 and 30. Thence, I run S. 89° 57' W. on true line. Variation same.
19.97	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. distant; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked 1/16 S on N face.
34.50	Canyon and Spring branch, course N.