

Chains	
38.50	1/16 S. on N. face. Fence and leave field.
39.92	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5 7/8 ft. dist.; raised mound of earth 1 7/8 ft. high, 8 3/4 ft. base over it and in E. pit drove stake 12 ins. in the ground 2 ft. long, 2 ins. square, marked 1/16 S. on N. face.
59.88	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 7/8 ft. dist.; raised mound of earth 1 7/8 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N face.
79.85	1/16 sec. cor. between secs. 23 and 24. Land, gently rolling. Soil, good.
79.90	East on random through center of sec. 24. Variation 19° East. Commencing at 7/8 sec. cor. between secs. 23 and 24. Set temporary corners at 20, 40 and 60 chains, and at Intersect E. boundary Township at 7/8 sec. cor. between secs. 24 and 19. Thence West on true line. Variation same.
19.98	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 7/8 ft. dist.; raised mound of earth 1 7/8 ft. high, 3 3/4 ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
59.95	Deposited charred stake 12 ins. in the ground for 7/8 sec. cor.; dug pits 18 x 18 x 12 ins. East and West of stake