

Chains	
80.00	East on random through S $\frac{1}{2}$ of Sec. 1.
80.00	Variation 20° East. Set temporary corner at 20, 40 and 60 chains, and at Intersect E. boundary sec. 12 lks. S. of 1/16 sec. cor. Thence S. 89° 55' W. on true line.
20.00	Descend gradually. Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
40.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16
60.00	S on N. face. Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{3}{4}$ ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16
80.00	S on N. face. 1/16 sec. cor. place of beginning. Land, slightly rolling. Soil, good. Grass, fair.
80.00	East on random through center of sec. 1. Variation 20° East. Commencing at sec. corner between secs. 1 and 2. Set temporary corners at 20, 40 and 60 chains and at Intersect E. boundary of sec. 15 lks. S. of $\frac{1}{2}$ sec. cor.,