

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains		
	sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.	
23.00	Dry ditch, course N.W.	-100
40.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.	
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.	
60.20	Dry bed of creek, course N.W.	
80.00	1/16 S. cor. at place of beginning. Land, rolling. Soil, 2nd rate.	
<hr/>		
	East on random through center of sec. 35. Variation 20° East. Beginning at ¼ sec. cor. between secs. 35 and 34 Set temporary corners at 20, 40 and 60 chains, and at	
79.90	Intersect E. bdy. sec. 20 lks. S. of 1/16 sec. cor., between sections 35 and 36. Thence S. 89° 51' West on true line. Variation same.	
	Descend.	
19.97	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of	