

Chains	
39.95	<p>of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{16}$ S on N. face.</p> <p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.</p>
59.93	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{16}$ S on N. face.</p>
65.00	<p>Dry bed of creek, course N.</p>
79.90	<p>$\frac{1}{4}$ Sec. corner at place of beginning.</p> <p>Land, level, mostly.</p> <p>Soil, good.</p>
79.92	<p>East on random through N$\frac{1}{2}$ of sec. 35.</p> <p>Variation 20° East.</p> <p>Commencing at $\frac{1}{16}$ sec. corner 20 chains N. of $\frac{1}{4}$ sec. cor., between secs. 34 and 35.</p> <p>Set temporary corners at 20, 40 and 60 chains, and at Intersect E. boundary sec. 5 lks. S. of $\frac{1}{16}$ sec. corner between secs. 35 and 36.</p> <p>Thence</p> <p>S. 89° 58' W. on true line.</p> <p>Variation same.</p>
19.98	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long.</p>