

## Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	square 12 ins. in the ground marked 1/16 S. on N. face.
24.75	Wagon road N and S.
39.85	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
59.76	Deposited charred stake 12 ins. in the ground for 1/16 S cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
79.70	To corner of beginning. Land, level. Soil, 1st rate.
	East on random through S½ of Sec. 11.
	Var. 20½° East.
	Commencing at 1/16 sec. cor. 20 chains N. of S.W. corner of sec. 11.
	Set temporary corners at 20, 40 and 60 chains, and at
79.80	Intersect E. bdy. of sec. 20 lks. N. of 1/16 sec. corner, Thence N. 89° 51' W. on true line.
	Var. 20° East.
5.00	Gulch N.
19.95	Set post 3 ft. long, 3 ins. square 24 ins. in the ground marked 1/16 S on W face for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base around post.
20.20	Wagon road course N.E.
24.85	Rail fence and leave pasture N and S.
39.75	Enter river bottom.
39.90	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. cor. and marked 1/16 S. on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post 5½ ft. dist and