

Chains	
55.70	Wagon road, course N.
59.85	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base around post.
70.90	Creek 15 lks. wide S.W.
79.80	To 1/16 corner and place of beginning. Land, level. Soil, 1st rate. Not cultivated.
79.70	East on random through center of section 11. Var. 20 1/2° East. Commencing at 3/4 sec. corner between secs. 10 and 11, Set temporary corners at 20, 40 and 60 chains, and at Intersect E. bdy. of sec. at corner. Thence West on true line.
19.92	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S on N face, from which A balm 12 ins. in diam. bears S. 75° W. 53 lks. dist., marked 1/16 S.B.T. No other tree in limits, and raise mound of stone around post. Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 3/4 sec. corner, marked 3/4 S on N face, from which A balm, 12 ins. in diam. bears S. 40° W., 77 lks. dist., marked 3/4 S B T.
39.85	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 3/4 sec. corner, marked 3/4 S on N face, from which A cherry 4 ins. in diam. bears N45°E. 18 lks. dist., marked 3/4 S.B.T.
47.50	Wagon road, course N.
51.50	Wagon road
59.77	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. corner marked 1/16 on N. face, from which