

Sub-Subdivisions, T. 2 N., R. 33-E.

Chains	
79.70	<p>A balm 18 ins. diam. bears S 45° W 35 lks. dist., marked 1/16 S.B.T. and raised mound of earth and stone around corner.</p> <p>To point of beginning.</p> <p>Land, mostly in river bottom.</p> <p>Soil, fair.</p> <p>Timber; Balm, pine and cherry and considerable underbrush.</p> <p>The remainder of this section is unfit for agricultural purposes.</p>
79.70	<p>East on random through S$\frac{1}{2}$ of sec. 2.</p> <p style="text-align: right;">Var. 20° East.</p> <p>Commencing at 1/16 sec. corner 20 chains N. of S.W. corner of sec. 2.</p> <p>Set temporary corners at 20, 40 and 60 chains and at</p> <p>Intersect E. boundary of sec., 14 lks. S. of 1/16 sec. corner.</p> <p style="text-align: center;">Thence</p> <p>S.89° 54' West, on true line.</p>
19.92	<p style="text-align: right;">Variation, same.</p> <p>Set post 3 ft. long, 3 ins. square 24 ins. in the ground marked 1/16 S on N. face for sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of post 5$\frac{1}{2}$ ft. dist. and raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base around post.</p>
39.85	<p>Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post 5$\frac{1}{2}$ ft. dist.; raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base around post.</p>
59.77	<p>Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 S cor., marked 1/16 S. on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post, 5$\frac{1}{2}$ ft. dist.; raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base around post.</p>
60.50	<p>Enter field N and S.</p>