

Chains	Long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
62.50	Dry branch of Tule Willows N. To point of beginning. Land, level. Soil, good. Not cultivated.
79.60	East on random through S $\frac{1}{2}$ of sec. 27. Variation 20° East. Commencing at 1/16 sec. corner, 20 chains N of S.W. corner of section 27, Set temporary corners at 20, 40 and 60 chains and at Intersect E. boundary 17 lks. N. of 1/16 sec. corner. Thence N. 89° 53' W. on true line.
19.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{3}{4}$ ft. high, 3 $\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face. Dry ditch, course N.
25.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{3}{4}$ ft. high, 3 $\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
59.70	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{3}{4}$ ft. high, 3 $\frac{3}{4}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face. To point of beginning. Land, level. Soil, 1st rate.
79.60	