

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	East on random through $S\frac{1}{2}$ of sec. 15.
	Variation $20\frac{1}{2}^{\circ}$ East
	Commencing at $1/16$ sec. corner 20 chains N. of S.W. cor.
	of sec. 15.
	Set temporary corners at 20, 40 and 60 chains, and at
80.00	Intersect E. boundary 7 lks. S. of $1/16$ sec. corner
	Thence
	S. $89^{\circ} 57'$ W. on true line.
	Variation $20^{\circ}$ East.
20.00	Deposited charred stake 12 ins. in the ground for $1/16$
	sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake
	$5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft.
	base over it and in E. pit drove stake 2 ft. long, 2 ins.
	square, 12 ins. in the ground marked $1/16$ S on N face.
40.00	Deposited charred stake 12 ins. in the ground for $1/16$ sec.
	cor.; dug pits 18 x 18 x 12 ins. E. and W. of stone $5\frac{1}{2}$
	dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base
	over it and in E. pit drove stake 2 ft. long, 2 ins.
	square, 12 ins. in the ground, marked $1/16$ S on N face.
60.00	Deposited charred stake 12 ins. in the ground for $1/16$ sec.
	cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$
	ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base
	over it and in E. pit drove stake 2 ft. long, 2 ins.
	square 12 ins. in the ground marked $1/16$ S on N face.
80.00	To point of beginning.
	Land, level.
	Soil, 1st rate.
	Not cultivated.
	East on random through center of sec. 15.
	Variation $20\frac{1}{2}^{\circ}$ East.
	Commencing at $\frac{1}{4}$ sec. cor. bet. secs. 15 and 16
	Set temporary corner at 20, 40 and 60 chains and at
80.00	Intersect E. bdy. 12 lks. S. of $\frac{1}{4}$ sec. cor.,
	Thence