

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	East on random through center of sec. 3.
	Variation 21° East.
	Commencing at $\frac{1}{4}$ sec. cor. between secs. 3 and 4
	Set temporary corners at 20, 40 and 60 chains, and at
79.80	Intersect E. bdy. at $\frac{1}{4}$ sec. cor.
	Thence
	West on true line.
	Variation 20° East.
19.95	Deposited charred stake 12 ins. in the ground for 1/16
	sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake
	5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft.
	base over it and in E. pit drove stake 2 ft. long, 2 ins.
	square 12 ins. in the ground marked 1/16 S on N. face.
39.90	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec.
	cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake,
	5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft.
	base over it and in E. pit drove stake 2 ft. long, 2 ins.
	square 12 ins. in the ground marked $\frac{1}{4}$ S on N. face.
44.00	Gulch, course S.
59.85	Deposited charred stake 12 ins. in the ground for 1/16
	sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of
	stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high,
	3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long,
	2 ins. square 12 ins. in the ground marked 1/16 S on N.
	face.
79.80	To point of beginning.
	Land, rolling.
	Soil, 1st rate.
	East on random through N $\frac{1}{2}$ of Sec. 3.
	Variation 21° East.
	Commencing at 1/16 sec. corner 20 chains N. of $\frac{1}{4}$ sec. cor.
	between secs. 3 and 4
	Set temporary corners at 20, 40 and 60 chains, and at
79.90	Intersect E. boundary 10 lks. N. of 1/16 sec. corner,