

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
80.00	To point of beginning. Land, mostly level. Soil, 1st rate.
<hr/>	
	East on random through S½ of sec. 28.
	Variation 21° East.
	Commencing at 1/16 sec. cor. 20 chains N. of S.W. corner sec. 28
	Set temporary corners at 20, 40 and 60 chains, and at
80.00	Intersect E. bdy. 10 lks N. of 1/16 sec. corner
	Thence
	N. 89° 56' West on true line.
	Variation 20° East.
2.75	Fence; course N and S.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
20.80	Tudie Willows Creek Dry, course N.W.
27.75	Fence and leave field N.E. and S.W.
40.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins square 12 ins. in the ground marked 1/16 S on N face.
50.00	Fence course N.E. and S.W.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. fist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins.