

Chains	
72.00	Wagon road, N and S. square 12 ins. in the ground marked 1/16 S on N face.
80.00	To point of beginning. Land, rolling. Soil, 1st rate.
79.90	East on random through center of sec. 28. Variation 20 1/2° East. Commencing at 1/4 sec. cor. between secs. 28 and 29 Set temporary corners at 20, 40 and 60 chains, and at Intersect E. bdy. at 1/4 sec. cor. Thence West on true line Variation, same.
7.00	Fence and enter field.
19.97	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
28.00	Tudle Willows Creek, N.W. Deposited charred stake 12 ins. in the ground for 1/4 sec. cor.; dug pits 18 x 18 x 12 ins. E and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/4 S on N face.
39.95	Deposited charred stake 12 ins. in the ground for 1/4 sec. cor.; dug pits 18 x 18 x 12 ins. E and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/4 S on N face.
42.75	Lane and wagon road N and S.
59.92	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
72.00	Fence, course N. Face.
79.90	To point of beginning.