

Chains	
79.72	<p>East on random through N$\frac{1}{2}$ of sec. 21. Variation 21° East Commencing at 1/16 sec. corner 20 chains N of $\frac{1}{4}$ sec. cor. between secs. 20 and 21. Set temporary corners at 20, 40 and 60 chains and at Intersect E. bdy. 25 lks. N of 1/16 sec. corner, Thence N. 89° 49' W. on true line, Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S on N face and rais- ed mound of stone 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it. Pits impracticable.</p>
39.86	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5$\frac{1}{2}$ ft. dist.; raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
59.79	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5$\frac{1}{2}$ ft. dist.; raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
79.72	<p>To point of beginning. Land, gently rolling. Soil, generally good. Not cultivated.</p>
79.72	<p>East on random through S$\frac{1}{2}$ of sec. 16. Variation 21° East Commencing at 1/16 sec. corner 20 chains N of S.W. corner of sec. 16 Set temporary corners at 20, 40 and 60 chains, and at Intersect E. boundary 50 lks. N. of 1/16 sec. corner.</p>