

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	<p style="text-align: center;">Thence</p> <p>N. 89° 39' W. on true line.</p>
19.93	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
39.86	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
59.79	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 feet. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
79.72	<p>To point of beginning.</p> <p>Land, level.</p> <p>Soil, good.</p> <p>Not cultivated.</p>
	<p>East on random through center of sec. 16.</p> <p style="text-align: right;">Variation 21° East.</p>
	<p>Commencing at ¼ sec. corner between secs. 16 and 17, Set temporary corners at 20, 40 and 60 chains, and at</p>
79.80	<p>Intersect E. bdy. 50 lks. N of ¼ sec. corner.</p> <p style="text-align: center;">Thence</p>
	<p>N. 89° 39' W. on true line.</p>
19.95	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S on N</p>