

Chains	
19.98	N. 89° 54' W. on true line
36.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground marked 1/16 S on N. face for $\frac{3}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it. Canyon bears S.
39.96	Top of ridge bears S. & set post 3 ft. long, 3 ins. square 24 ins. in the ground for $\frac{3}{4}$ sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it, and marked post $\frac{3}{4}$ S. on N. face.
59.94	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of post $5\frac{1}{2}$ ft. distant and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.
79.92	Descend. To point of beginning. Land very rolling. Soil, generally good. Some alkali. Not cultivated.
80.00	Intersect E. boundary at 1/16 corner Thence
20.00	West on true line. Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S. on N. face; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.

-100