

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
40.00	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. corner marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base around it.
45.00	Canyon, course S. Ascend.
60.00	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. corner marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base around it.
80.00	To point of beginning. Land, rolling. Soil, 1st rate. Not cultivated.
<hr/>	
	East on random through S 1/2 of sec. 32. Variation 20 1/2° East Commencing at 1/16 sec. corner 20 chains N. of S.W. cor. of sec. 32 Set temporary corners at 20, 40 and 60 chains, and at
79.90	Intersect E. boundary at corner to 1/16 sec. Thence West on true line
12.80	Dry creek.
19.93	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
38.20	Wagon road bears N. and S.
39.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long,