

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
59.85	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. distant and raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
75.50	Wagon road course N and S.
79.80	To point of beginning.
	Land, level.
	Soil, 1st rate.
	Not cultivated.
<hr/>	
	East on random through N½ of sec. 32.
	Variation 21° East
	Commencing at 1/16 sec. corner 20 chains N. of ¼ sec. corner,
	Set temporary corners at 20, 40 and 60 chains and at
79.88	Intersect E. boundary at 1/16 sec. corner
	Thence
	West on true line.
16.20	Tudie Willows Creek dry, course N.
19.97	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
26.70	Dry gulch and bed of creek.
39.94	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square, 12 ft. in the ground marked 1/16 S on N. face.
59.91	Deposited charred stake 12 ins. in the ground for 1/16