

## Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	<p>East on random through <math>S\frac{1}{2}</math> of sec. 20.</p> <p style="text-align: right;">Variation <math>20^{\circ}</math> East.</p> <p>Commencing at <math>1/16</math> sec. corner 20 chains N of S.W. corner of sec. 20.</p> <p>Set temporary corners at 20, 40 and 60 chains, and at</p>
79.76	Intersect E. bdy. at $1/16$ sec. corner,
	Thence
	West on true line
13.00	Wagon road N.
19.94	<p>Deposit charred stake 12 ins. in the ground 10 lks. S. of true corner for <math>1/16</math> witness corner; dug pits 18 x 18 x 12 ins. E. and W. of stake <math>5\frac{1}{2}</math> ft. dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked W.C. <math>1/16</math> S. on N. face.</p>
19.95	Creek course N.
39.88	<p>Deposited charred stake 12 ins. in the ground for <math>1/16</math> sec. cor.; dug pits 18 x 18 x 12 ins. E. and W. of stake <math>5\frac{1}{2}</math> ft. dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked <math>1/16</math> S on N. face.</p>
59.82	<p>Deposited charred stake 12 ins. in the ground for <math>1/16</math> sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake <math>5\frac{1}{2}</math> ft. distant; raised mound of earth <math>1\frac{1}{2}</math> ft. high <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked <math>1/16</math> S on N. face.</p>
79.76	<p>To point of Commencement.</p> <p>Land, level. Soil, 1st rate.</p>
	<p>East on random through center of sec. 20.</p> <p style="text-align: right;">Variation <math>19-3/4^{\circ}</math> E.</p> <p>Commencing at <math>\frac{1}{4}</math> sec. corner between secs. 19 and 20</p> <p>Set temporary corners at 20, 40 and 60 chains, and at</p>