

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	Thence
	N. 89° 42' W. on true line.
14.90	Wagon road course N. and S.
18.00	Enter field.
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. distant; raised mound of stone and earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
22.00	House bears N. 50 lks. distant.
25.00	Tudie Willows Creek, 2 lks. runs North.
39.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. distant; raised mound of earth 1½ ft. high 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
54.00	Dry bed of creek N.W.
59.85	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
79.80	To point of beginning. Land, rough or rolling. Soil, good.
	East on random through S½ of sec. 17. Variation 20° East. Commencing at 1/16 sec. corner 20 chains N. of S.W. cor. of sec. 17, Set temporary corners at 20, 40 and 60 chains, and at
80.00	Intersect E. boundary 12 lks. S. of 1/16 sec. corner