

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 inches square 12 ins. in the ground marked 1/16 S on N. face.
39.90	Deposited charred stake 12 ins. in the ground for 1/4 sec. corner; dug pits 18 x 18 x 12 ins. E&W. of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/4 S on N. face.
39.95	Wagon road bears N.W.
59.85	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
65.00	Wagon road N. and S.
79.80	To point of beginning. Land, rolling. Soil, 1st rate. Not cultivated.
	East on random through N½ of sec. 17.
	Var. 20° East.
	Beginning at 1/16 sec. corner 20 chains N of 1/4 section corner between secs. 17 and 18
	Set temporary corners at 20, 40 and 60 chains, and at
79.60	Intersect E. boundary at 1/16 sec. corner
	Thence
	West on true line.
16.20	Wagon road bears N and S.