

Chains	<p>long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
39.86	<p>Deposited charred stake 12 ins. in the ground for 1/4 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. distant; raised mound of earth 1 3/4 ft. high 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/4 S on N. face.</p>
51.00	<p>Wagon road bears N.W. deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. distant; raised mound of earth 1 3/4 ft. high, 3 3/4 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.</p>
59.79	<p>Road bears N and S. To point of beginning.</p>
79.72	<p>Land, rolling. Soil, 1st rate. Not cultivated.</p>
Oct. 22, 1887	
East on random through S 1/2 of sec. 5.	
Var. 21° East.	
Commencing at 1/16 sec. corner between secs. 5 and 6, 20 chains N. of sec. corner to secs. 5, 6, 7 and 8.	
Set temporary corners at 20, 40 and 60 chains, and at	
Intersect E. boundary 50 lks. N. of 1/16 sec. corner	
Thence	
N. 80° 39' W. on true line	
Fence bears N. and S.	
19.98	<p>Set basalt stone 10 x 9 x 8 ins., 6 ins. in the ground for 1/16 sec. corner, marked 1/16 on N. face and raised</p>
mound of earth and stone 2 ft. high, 4 3/4 ft. base over it.	
Leave river bottom and ascend.	
39.96	<p>Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. corner, marked 1/16 on N. face and raised</p>