

Chains	
52.00	Face. Gulch bears S.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. distant; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
64.00	Top of ridge bears N.
80.00	To point of beginning. Land, rolling. Soil, 2nd rate. Little grass.
80.12	East on random through N 1/2 of sec. 5. Variation 21 1/2° East. Beginning at 1/16 sec. corner 20 chains N. of 1/2 sec. corner between secs. 5 and 6. Set temporary corners at 20, 40 and 60 chains, and at Intersect E. boundary at 1/16 sec. corner Thence
20.02	West on true line. Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. distant; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
40.06	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. & W. of stake 5 1/2 ft. distant; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
47.00	Having, course S.
60.09	Deposited charred stake 12 ins. in the ground for 1/16

+200

-150

-50