

Chains	4 1/2 ft. base over it and in E. pit drove stake 2 ft. long	2 ins. square 12 ins. in the ground marked 1/16 S.C.C.	on N. face.	Land, level.	Soil, 1st rate.	Not cultivated.
20.00	Deposited charred stake 12 ins. in the ground for 1/16	sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of	stake 5 3/4 ft. distant; raised mound of earth 1 1/2 ft. high,	3 3/4 ft. base over it and in E. pit drove stake 2 ft. long	2 ins. square, 12 ins. in the ground marked 1/16 S on N.	face.
40.00	Deposited charred stake 12 ins. in the ground for 1/4 sec.	corner; dug pits 18 x 18 x 12 ins. E. and W. of stake	5 3/4 ft. distant; raised mound of earth 1 1/2 ft. high, 3 3/4	ft. base over it and in E. pit drove stake 2 ft. long,	2 ins. square 12 ins. in the ground marked 1/4 S on N.	face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16	sec. cor.; dug pits 18x18x12 ins. E. and W. of stake 5 3/4	ft. distant; raised mound of earth 1 1/2 ft. high, 3 3/4 ft.	base over it and in E. pit drove stake 2 ft. long, 2 ins.	square 12 ins. in the ground marked 1/16 S on N. face.	Head of draw bears S.W.
65.00	Intersect W. boundary Township at 1/4 sec. corner in E.	boundary of sec. 36, T. 2 N., R. 33 E.	Land, slightly rolling.	Soil, 1st rate.	Not cultivated.	West on true line through N 1/2 of sec. 31.
76.60	Intersect W. boundary Township at 1/4 sec. corner in E.	boundary of sec. 36, T. 2 N., R. 33 E.	Land, slightly rolling.	Soil, 1st rate.	Not cultivated.	Variation 20 3/4 East.

-50