

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E and W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
76.20	Intersect West boundary Township 1.28 chains N. of ¼ sec. corner to E. boundary of Sec. 25, Tp. 2 N. R. 32 E. and set charred stake 12 ins. in the ground for 1/4 sec. closing corner; dug pits 18 x 18 x 12 ins. N., E. & S. of stake 5½ ft. distant; raised mound of earth 2 ft. high, 4½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked ¼ S.C.C. on E. face. Land, rolling. Soil, 1st rate. Not cultivated.
West on true line through N½ of sec. 30. Variation 20° East.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E and W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E pit drove stake 2 ft. long, 2 inches square 12 ins. in the ground marked 1/16 S on N. face.
40.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.
45.30	Wagon road bears N and S.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. E and W of stake 5½ ft. dist; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.
76.00	Intersect E. bdy. of sec. 25, 18.26 chains S of cor. to secs. 24 & 25, Tp.2,N.R. 32 E. and Deposited charred stake 12 ins. in the ground for 1/16