

sec. closing corner; dug pits 18x18x12 ins. N., E. and S. of stake 5 1/2 ft. distant; raised mound of earth 2 ft. high, 4 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S.C.C. on E. face.

Land, rolling.

Soil, 1st rate. Not cultivated.

October 24, 1887.

West on true line through S 1/2 of sec. 19.

Variation 20° East.

10.25 Draw bears N.

20.00 Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. & W. of stake, 5 1/2 ft. distant; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.

40.00 Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake 5 1/2 ft. distant; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.

60.00 Deposited charred stake 12 ins. in the ground for 1/16 section corner; dug pits 18x18x12 ins. E and W of stake 5 1/2 ft. distant; raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/16 S on N face.

76.10 Intersect W. boundary Township 19.95 chains N of closing corner to secs. 18 and 30, and Deposited charred stake 12 ins. in the ground for 1/16 sec. closing corner; dug pits 18x18x12 ins. N., E. and S. of

-50