

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
	West on true line through $S\frac{1}{2}$ of sec. 18. Variation 20° East.
20.00	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for $1/16$ sec. corner marked $1/16$ S. on N. face and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
40.00	Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $1/16$ S on N. face.
44.15	Wagon road bears N.W.
54.00	" " " N.W.
57.25	Tudie Willows Creek 5 lks. N.W.
60.00	Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ft. square 12 ins. in the ground marked $1/16$ S on N. face.
76.70	Intersect W. boundary Township, 20.10 chains North of Closing Corner to secs. 18 and 19, and Deposited charred stake 12 ins. in the ground for $1/16$ sec. closing corner; dug pits 18 x 18 x 12 ins. N.E. and S. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $1/16$ S.C.C. on E. face. Land, rolling. Soil, 1st rate. Partly cultivated.
	West on true line through center of sec. 18. Variation $20\frac{1}{4}^{\circ}$ East.
20.00	Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft.

-50