

Sub-Subdivisions, T. 2 N., R. 33 E.

Chains	
38.00	Gulch bears N.
40.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. corner; dug pits 18 x 18 x 12 ins. E. and E. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.
58.00	Gulch bears N.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E. and W. of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.
76.77	Intersect E. boundary of sec. 12, T. 2 N., R. 32 E., 3.90 chains N. of $\frac{1}{2}$ sec. corner and set post 3 ft. long, 3 ins. square, 24 ins. in the ground marked $\frac{1}{4}$ S. on N. face for $\frac{1}{4}$ Sec. closing corner; dug pits 18 x 18 x 12 ins. N., E. and S. of post $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it. Land, rolling. Soil 1st rate. Not cultivated. The $N\frac{1}{2}$ of this section is not adapted to agriculture.
<p>Field Notes of the Survey of N. Boundary of T. 2 N., R. 33 E. Survey by Jas. P. Currin &amp; Jas. E. Noland, under Special Contract, dated May 4, 1887.) (S. bdy. T. 3 N., R. 33 E.)</p>	
<p>Beginning at Township cor. T. 2 &amp; 3, N.Rs. 32 &amp; 33 East, which is a stone in a stone mound, we ran S. 89° 46' E. on a true line on S. boundary of sec. 31. Variation 20° East.</p>	
31.75	Wild Horse Creek 25 lks. Course S.W.
32.64	Found meander corner to secs. 31 & 6, a stone 14 x 10 x 8 ins. firmly set in the ground with a pit 8 lks. E., partly filled mound mostly washed away; stone marked U.R.M.C. on E. face.

-100