

Chains

33.54 Pendleton & Walla Walla R.R. Course N.E. and S.W.

To 1/2 sec. corner, a stone 10 x 8 x 7 ins., 7 ins. in the

Ground with pits E & W 5 1/2 ft. distant, partly filled.

Stone marked 1/2 on N. face, mound about gone.

Summit of hill, course N.W.

58.50 Gulch

75.65 To post 4 ft. long by 4 inches square firmly set in ground;

corner sections 5 & 6, marked S.32, T.3. N. on N.E.;

S31 R.33 E. on N.W.; S.5 1/2 N and D.R. on S.E.; and S.6

on S.W. faces; no notches. I cut 5 notches on E. and 1

on W. faces, with pits in each sec. 5 1/2 ft. dist.; mound

mostly blown away.

Land, rolling. Soil, 2nd rate. Some grass.

S.89° 46' E. on S. boundary Sec. 32.

Variation 21° 30' East.

3.90 Passed closing cor. secs. 31 & 32.

4.50 Gulch, course S.E.

40.10 Found 1/2 sec. cor., a stone 10 x 8 x 6 ins., 7 ins. in the

Ground, marked 1/2 on N. face, D.R. on S. face. Pits and

mound in good condition.

51.25 Enter road to Pendleton & Athena, course N.E. and S.W.

60.20 Leave " " " " " " " " " " " "

64.00 Small gulch, course S.W.

80.15 To corner secs. 4 & 5, a basalt stone 10x8x7 ins. firmly

set in the ground marked with 4 notches on E. and 2 on

W. edges; D.R. on S. face; pits in each sec. 5 1/2 ft.

distant in good condition; mound badly scattered by stock

and wind.

Land, rolling.

Soil, 2nd rate.

Very little grass.

-50

-20

150