

Chains

1.40	To closing cor. to secs. 34 & 35.
40.05	To $\frac{3}{4}$ cor. pits with md. between stake gone. No material to reset cor.
80.15	To sec. cor. secs. 1 & 2, which is a post 4 ft. long by 4 ins. square, marked S.36, T.3 N. on N.E.; S.1 T. 2 N. on S.E.; S.2 R.33 E. D.R. on S.W.; S.35 on N.W. faces. I cut 1 notch on E. & 5 on W. edges. Pits N.E., S.W. & N.W. $5\frac{1}{2}$ ft. dist., partly filled, mound scattered. Land, rolling. Soil, 2nd rate. Some grass.
S.89° 46' E. on S. bdy. of sec. 35.	
Var. 21° East.	
1.10	Closing cor. secs. 35 & 36.
5.50	Gulch, course N.W.
20.00	1/16 cor. in good condition.
36.50	Road, course N.W. & S.E.
40.00	Found pits & md. between, all in good condition. Stake gone.
60.00	Passed 1/16 cor. in good condition.
80.10	To cor. Townships 2 & 3 N. R's. 33 & 34 E. a post 4 ft. long, 4 ins. square, firmly set in ground, marked S. 31 T. 3 N. on N.E.; S.6 R.34 E. on S.E.; S.1, R.33 E. on S.W.; S.36, T. 2 N. on N.W. faces. No notches. I cut 6 notches on N.E. S & W, edges of post. Pits in each sec. $5\frac{1}{2}$ ft. distant in good condition only partly filled mound, about all gone, blown away and stamped down by stock. Land, rolling and broken. Soil, 2nd rate. Some grass. Land being plowed. Surveyed April 25th, 1890.