

57.59	Chains	Top of bluff, bears E. and W.; ascend gradually to	80.46	The 1/2 cor. bet. secs. 10 and 15.
Boundaries of Sec. 10, T. 2 N., R. 33 E.				
Latitudes, departures and closing errors				
Line designated		True bearing	Dist.	Latitudes
Departures		E. W.		
W. bdy. sec. 10	(N.0°25'W.	40.24	Chs.	80.52
N. bdy. sec. 10	East	40.58	Chs.	80.52
E. bdy. sec. 10	S.0°13'W.	80.44	Chs.	80.44
S. bdy. sec. 10	(N.89°55'W.	40.16	Chs.	40.16
convergency		40.07	Chs.	40.07
Totals		80.88	Chs.	80.88
Error in Lat.		80.73	Chs.	80.82
Error in Dep.		0.15	Chs.	0.09
Survey of Cemeteries in Sec. 10, T. 2 N., R. 33 E.				
Chains				
19.55	From the center of sec. 10.	S.18°00'E., through SE 1/4 of sec. 10.	To NW. cor. of cemetery No. 1.	Set an iron post, 3 ft. long, 2 ins. diam., 28 ins. in
2.619	Thence	East, on N. bdy. of cemetery.	Set an iron post, 3 ft. long, 1 in. diam., 26 ins. in the	Ground, for cor. No. 1, Cemetery No. 1, with brass cap
2.773	Thence	S.9°15'W., on E. bdy. of cemetery.	Set an iron post, 3 ft. long, 1 in. diam., 26 ins. in the	
<div style="display: flex; justify-content: space-around;"> <div style="text-align: center;"> <p>1917</p> <p>COR 1</p> <p>COR 2</p> </div> <div style="text-align: center;"> <p>1917</p> <p>COR 1</p> <p>COR 2</p> </div> </div>				