

T. 2 N., R. 34 E. (No. boundary)

Chains	
	N. 89° 42' East on true line on the North Boundary of Sec. 1.
	Var. 19° 15' East.
40.00	Set post and made earth mound for $\frac{1}{4}$ Section corner.
80.00	To corner for Tps. 2 & 3, N.Rs. 34 & 35 East, Willamette Meridian.
	Land, rolling. Soil, 1st rate. Good grass.
	June 1st, 1871.
<hr/> <p>Field Notes of the Survey of the Subdivisional Lines of T. 2 N., R. 34 E., by Z. F. Moody, under his contract No. 145, dated April 23rd, 1871.</p> <hr/>	
	North between Secs. 35 and 36.
	Var. 21° East.
40.00	Set post for $\frac{1}{4}$ Sec. corner, from which
	A Pine, 30 ins. in diam. bears N.50°W. 50 lks.
	" " 20 " " " " S.20°W. 75 lks.
52.50	La Grand and Pendleton road N.W. & S.E.
80.00	A Pine 20 ins. in diam. for corner to secs. 25, 26, 35 & 36..
	Land, rolling.
	Soil, 1st rate. Good quality of grass.
<hr/> <p>East on random between secs. 25 &amp; 36.</p>	
	Var. 21° East
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.10	Intersected N & S line 50 lks S. of corner
	S.89° 39' West on true line.
40.05	Set stone 14 x 12 x 9 for $\frac{1}{4}$ Sec. corner.
80.10	To corner.
	Land, mostly rolling. Soil, 1st rate. Good grass.
<hr/> <p>North between Secs. 25 &amp; 26.</p>	
12.00	Brook, 4 lks. wide, flows N. E.
40.00	Set stone 18 x 16 x 12 for $\frac{1}{4}$ Sec. corner.
80.00	Set stone 16 x 16 x 10 for corner to secs. 25, 26, 23 & 24.

50