

Subdivisions, T. 2 N., R. 34 E.

Chains		
	on river bottom.	
	North between secs. 34 & 35.	
40.00	Set stone 16 x 14 x 5 for $\frac{1}{4}$ sec. corner.	
80.00	Set post and made stone mound for corner to secs. 34, 35, 26 & 27.	-100
	Land, broken.	
	Soil, good, 2nd rate. Good grass.	
	East on random between secs. 26 & 35.	
	Var. 22° East.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.	
80.00	Intersected N. & S. line 23 lks. S. of cor.	
	S. 89° 50' West on true line.	
18.00	La Grand and Pendleton road, course N.W. and S.E.	
40.00	Set stone 16 x 12 x 7 for $\frac{1}{4}$ sec. corner.	
78.00	Brook, 4 lks. wide, flows N.W.	-150
80.00	To corner	+ 50
	Land, broken. Soil, 1st rate. Good grass.	
	North between secs. 26 & 27.	
4.00	Brook, 6 lks. wide, flows N.W.	-40
40.00	Set stone 14 x 14 x 9 for $\frac{1}{4}$ sec. corner.	-70
68.50	Brook, 7 lks. wide, flows N.W.	-40
80.00	Set stone 18 x 14 x 10 for corner to secs. 26, 27, 22 & 23.	
	Land, broken.	
	Soil, 1st rate. Good grass.	
	East on random between secs. 23 & 26.	
	Variation 21° 30' East.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner,	
80.10	Intersected N. & S. line 14 N. of corner.	
	N. 89° 54' West on true line.	
40.05	Set stone 18 x 14 x 9 for $\frac{1}{4}$ sec. corner.	