

Subdivisions, T. 2 N., R. 34 E.

Chains		
66.00	La Grand and Pendleton road, course N.W. & S.E.	
80.10	To corner.	
	Land, rolling. Soil, 1st rate. Good grass.	
<hr/>		
	North between secs. 22 & 23.	
18.50	La Grand and Pendleton road, course N.W. & S.E.	
40.00	Set stone 14 x 14 x 8 for $\frac{1}{4}$ sec. corner.	
80.00	Set stone 16 x 12 x 10 for corner to secs. 14, 15, 22 & 23.	-150
	Land, broken.	
	Soil, good 2nd rate. Good grass.	
<hr/>		
	East on random between secs. 14 & 23.	
	Variation 21° 30' East.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.	
80.04	Intersected N & S line 37 lks. N of cor.	
	N. 89° 44' West on true line.	
26.50	Brook, 2 lks. wide, flows N.	-75
40.02	Set stone 18 x 17 x 10 for $\frac{1}{4}$ sec. corner.	
80.04	To corner.	
	Land, rolling. Soil, 1st rate. Good grass.	
<hr/>		
	North bet. secs. 14 & 15.	
40.00	Set stone 15 x 14 x 4 for $\frac{1}{4}$ sec. corner.	
65.00	Brook, 3 lks. wide, flows N.W.	-75
80.00	Set post and made stone mound for sec. corner.	-45
	Land, sloping north. Soil, 1st rate. Good grass.	
<hr/>		
	East on random between secs. 11 & 14.	
	Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.	
79.97	Intersected N. & S. line 12 lks. S. of corner.	
	S. 89° 55' West on true line.	
32.25	Brook, 5 lks. flows N.W.	
39.98	Set post and made stone mound for $\frac{1}{4}$ Sec. corner.	