

Subdivisions, T.2 N., R. 34 E.

Chains		
80.00	Set post and made mound of stone for corners to secs. 21, 22, 15 & 16. Land, sloping north. Soil, 1st rate. Good grass.	100
East on random between secs. 15 & 22. Var. 20° East.		
40.00	Set temporary 1/4 sec. corner.	
79.94	Intersected N. & S. line at corner. West on true line.	
20.40	Brook, 4 lks., flows N.W.	
39.97	Set stone 14 x 14 x 4 for 1/4 sec. corner.	
55.40	La Grand and Pendleton road, course N.W. & S.E.	
65.00	Brook, 7 lks., flows N.	
79.94	To corner. Land, rolling. Soil, 1st rate. Good grass.	
North between secs. 15 & 16,		
25.50	La Grand and Pendleton road, N.W. & S.E.	
40.00	Set post and stone mound for 1/4 Sec. cor. U. S. Post Office, Cayuse, bears W. about 20 chains.	
40.50	Brook, 10 lks., flows N.W.	
80.00	Set post and made earth mound for corner to secs. 9, 10, 15 & 16. Land, level. Soil, 1st rate.	
East on random between secs. 10 & 15. Variation 20° 30' East		
40.00	Set temporary 1/4 Sec. corner.	
80.00	Intersected N. & S. line 26 lks. S. of Corner. S. 89° 49' West on true line.	
40.00	Set stone 14 x 12 x 7 for 1/4 Sec. corner.	
80.00	To corner. Land, level. Soil, 1st rate. Good grass.	