

Subdivisions, T. 2 N., R. 34 E.

Chains		
	East on random between Secs. 28 & 33. Variation 21°30' East	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.	
80.08	Intersected N. & S. line 24 lks. N. of corner. N. 89° 50' West on true line.	
33.50	Brook, 8 lks. wide, flows N.	-80
40.04	Set stone 14 x 14 x 4 for $\frac{1}{4}$ Sec. corner.	+40
80.08	To corner. This line passes across ridges. Soil, 1st rate. Good grass.	+100
<hr/>		
	North between secs. 28 & 29.	
40.00	Set stone 14 x 12 x 9 for $\frac{1}{4}$ Sec. cor.	
80.00	Set stone, 18 x 16 x 4 for corner to secs. 28, 29, 20 & 21.	-40
	Land, sloping North.	
	Soil, 1st rate. Good grass.	
<hr/>		
	East on random between secs. 21 & 28.	
	Var. 20°30' East.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.	
79.96	Intersected N. & S. line 12 lks. S. of cor. S. 89° 55' West on true line.	
39.98	Set stone 18 x 10 x 9 for $\frac{1}{4}$ Sec. corner.	
75.00	Brook, 8 lks. wide, flows N.W.	-100
79.96	To corner.	+ 75
	The land along this line is of a good quality and produces good grass.	
<hr/>		
	North between Secs. 20 & 21.	
3.00	Indian house bears E. about 10 chains.	
38.84	To brook, 10 lks. wide, flows N.W.	-70
40.00	Set post and made stone mound for $\frac{1}{4}$ Sec. corner.	
80.00	Set post and made stone mound for cor. to secs. 20, 21, 16 & 17.	