

Chains

GENERAL DESCRIPTION

Exterior lines of one North R. 35 E. passes over broken and uneven ground with scattering timber and a good growth of grass well watered and only adapted for grazing.

T. 1 N.R. 34 E. is very broken and well watered and is well adapted to grazing. T. 2 N.R. 33 E. is level and is well adapted to agricultural purposes. T. 2 N. 34 E.  $N\frac{1}{2}$  good, tillable;  $S\frac{1}{2}$  adapted to grazing.

---

Field Notes of the Survey of the Exterior Lines of T. 3, N., R. 34 East, by Currin & Noland, under their Special Contract, dated May 4th, 1887.

---

From cor. to Tps. 3 N. Rs. 34 & 35 E., I run W. on random on S. bdy. of T. 3 N. R. 34 E.

Variation  $20^{\circ}$  East.

I set temporary sec. and  $\frac{1}{4}$  Sec. cors. at each 80 & 40 chs. at 5 miles and 74.56 chs. Intersect West bdy. 196. lks. S. of cor. to Tps. 2 & 3, N. Rs. 33 & 34 E.

Thence, I run

S.  $89^{\circ} 46'$  E. on true line on S. bdy. Sec. 31.

Var.  $20^{\circ} 15'$  East.

14.56 Deposited a charred stake 12 ins. in the ground for  $\frac{1}{16}$  sec. cor.; dug pits 18 x 18 x 12 ins., E. & W. of cor.  $5\frac{1}{2}$  ft. dist., and raised a mound of earth  $1\frac{1}{2}$  ft. high,  $3\frac{1}{2}$  ft. base over it. In E. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked  $\frac{1}{16}$  S. on N. face.

34.56 Deposited a charred stake 12 ins. in the ground for  $\frac{1}{4}$  sec. cor.; dug pits 18 x 18 x 12 ins. E. & W. of cor.,  $5\frac{1}{2}$  ft. dist. and raised a mound of earth  $1\frac{1}{2}$  ft. high,  $3\frac{1}{2}$  ft. base over it. In E. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked  $\frac{1}{4}$  S on N. face.