

## Exteriors, T. 3 N., R. 34 East.

Chains	
	of stone over it. Pits impracticable.
60.00	Set a basalt stone 14 x 12 x 12 ins., 10 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face; raised a mound of stone over it. Pits impracticable.
79.80	Dry ditch, course S.
80.00	Set a basalt stone 12 x 9 x 7 ins., 8 ins. in the ground for cor. to secs. 35 & 36, marked 5 notches on W. and 1 notch on E. edges. Raised stone around cor. Pits impracticable.
	Land, rolling. Soil, 3rd rate. No timber. Poor grass.
	<hr/> South 89° 46' E. on S. bdy. Sec. 36. Var. 22° East.
20.00	Set a post 36 x 3 x 3 ins., 12 ins. in the ground for 1/16 Sec. cor., marked 1/16 S on N. face; dug pits 18x18x12 ins. E & W. of cor. 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base around post.
40.00	Set a post 36 x 3 x 3 ins., 12 ins. in the ground for ¼ sec. cor., marked ¼ S on N. face; dug pits 18x18x12 ins. E & W. of cor. 5½ ft. dist and raised a mound of earth 1½ ft. high, 3½ ft. base around post.
60.00	Canyon. Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E & W. of cor. 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.
80.00	To cor. to Tps. 3 N.R. 34 & 35 E. Land, rolling. Soil, 2nd rate. Poor grass.
	August 17, 1887.