

Exteriors, T. 2 N., R. 34 East

Chains		
	Beginning at the cor. to Tps. 1 & 2, N. R. 34 & 35 E., I run N. on true line bet. Tps. 2 N. Rs. 34 & 35 E. N. bet. secs. 31 & 36.	
	Var. 20° East	
5.00	Summit. Descend	+20
40.00	Set a basalt stone 18 x 16 x 12 ins., 12 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ on W. face. Raised a mound of stone alongside. Pits impracticable.	
51.50	Brook, 2 lks. wide, course N. 20° E.	-400
65.00	Summit of ridge. Course N.E.	+300
74.00	Gulch, course E.	-150
80.00	Set a basalt stone 15 x 14 x 12 ins., 10 ins. in the ground on summit of a point for cor. to secs. 25, 30 31, & 36, marked 1 notch on S. and 5 on N. edges. Raised a mound of stone alongside; pits impracticable. Land, mountainous 80 chs. Soil, 3rd rate. Scattering timber, pine.	+300
North bet. secs. 25 & 30.		
Var. 27° East.		
15.00	Canyon, course N.E.	-400
30.00	Top of hill " "	+600
40.00	Set a basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face. Raised a mound of stone alongside. Pits impracticable.	
42.00	Canyon, course N.E.	-500
55.00	Ridge, " " "	+400
75.00	Canyon " " "	-400
80.00	Set a basalt stone 20 x 10 x 8 ins., 15 ins. in the ground for cor. to secs. 24, 25, 19 & 30, marked 2 notches on S. and 4 on N. edges. Raised a mound of stone alongside; pits impracticable. Land, mountainous 80 chs. Soil, rocky, 4th rate. Poor grass. No timber.	