

Subdivisions, T. 2 N., R. 34 East

Chains		
	Ascend.	
13.00	Top of mountain & prairie N.	+600
39.75	Set basalt stone 10 x 8 x 8 ins., 6 ins. in the ground for $\frac{1}{4}$ S. cor., marked $\frac{1}{4}$ on N. face and raised mound of stone over it. Pits impracticable.	
76.50	Gulch N.	-300
79.50	Cor. to secs. 25, 26, 35 & 36. Land, rough and mountainous 79.50 chs. Soil, 4th rate and rocky. Timber in canyons. Bunch grass good.	
<hr/>		
	North between secs. 25 and 26. Var. 18° East	
20.00	Gulch N 10° W.	-150
40.00	Set basalt stone 16 x 10 x 10 ins., 10 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ on W. face; raised mound of stone over it. Pits impracticable.	
49.00	Gulch, N.E.	-100
80.00	Set basalt stone 16 x 8 x 6 ins., 12 ins. in the ground for cor. to secs. 23, 24, 25 & 26, marked with 2 notches on S. and 1 notch on E. edges; raised a mound of stone over it; pits impracticable. Land, mountainous, 80 chs. Soil, 3rd rate and rocky. Timber, pine and fir scattering. Bunch grass, good.	
<hr/>		
	East on random bet. secs. 24 and 25. Var. 19-3/4° East.	
40.00	Set temporary $\frac{1}{4}$ Sec. cor. and at	
79.25	Intersect Tp. line 56 lks. S. of cors. to secs. 24, 25, 19 and 30. Thence, S. 89° 36' W. on true line. Var. 21° East.	
14.50	Canyon, N.	-500