

Subdivisions, T. 2 N., R. 34 E.

Chains		
	East on random bet. secs. 12 & 13. Var. $19\frac{1}{4}^{\circ}$ East.	
40.00	Set temporary $\frac{1}{4}$ Sec. cor. and at	
79.96	Intersect Tp. line 40 lks. N. of cor. to secs. 12, 13, 7 & 18.	
	Thence,	
	N. $89^{\circ} 43'$ W. on true line. Var. $20^{\circ}$ East.	
	Ascend.	
27.46	Summit N.	+400
39.46	Gulch, N.E.	-400
39.98	Set basalt stone 9 x 8 x 7 firmly in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face; raised mound of stone over it; pits impracticable.	
60.20	Wagon road on summit N.W.	+600
72.00	Gulch, N.W.	-350
79.96	Cor. to secs. 11, 12, 13 & 14. Land, rough and mountainous 79.96 chs. Soil, 2nd rate, some rock. Grass good.	
	North between secs. 11 & 12. Var. $19\frac{1}{4}^{\circ}$ East.	
9.00	Gulch N.W.	-50
19.00	Summit ridge W.	+200
20.00	Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins., N & S of cor., $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In N. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W face.	
24.00	Wagon road N.W.	
40.00	Set basalt stone 12 x 8 x 6 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 ins. N & S of stone, $5\frac{1}{2}$ ft. dist., and raised mound of stone and earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
44.15	Gulch N.W.	-100