

Subdivisions, T. 2 N., R. 34 E.

Chains		
	Soil, 2nd rate, rocky. Timber, pine and fir and thick snow brush.	
	North bet. secs. 26 & 27. Var. 21° East.	
4.00	Canyon and enter snow brush, N.W.	-250
31.00	Top hill N.W.	+400
39.50	Leave snow brush.	
40.00	Set basalt stone 12 x 8 x 7 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 ins. N and S of stone $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
54.75	Canyon, N.W.	
79.50	Old stage road N.W.	
80.00	Set basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for cor. to secs. 22, 23, 26 & 27, marked with 2 notches on S and E edges; dug pits 18 x 18 x 12 ins. in each sec., $5\frac{1}{2}$ ft. dist. and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Land, mountainous, rough, 80.00 chs. Soil, 1st rate. Grass, good.	
	East on random bet. secs. 23 & 26. Var. 20° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
80.00	Intersect N and S line at cor. to secs. 23, 24, 25 & 26. Thence, West on true line. Var. 19-3/4° East.	
5.00	Summit ridge N.W.	+300
30.00	Gulch N.	-100
40.00	Set basalt stone 14 x 8 x 7 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face; raised mound of stone over it. Pits impracticable. Ascend.	