

Subdivisions, T. 2 N., R. 34 E.

Chains		
	Var. 19° 50' East	
11.50	Top of hill N.	+100
26.70	Gulch, N.	-100
30.75	Old wagon road N.W.	
40.03	Set basalt stone 12 x 10 x 6 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face and raised mound of stone over it. Pits impracticable.	
44.00	Gulch, N.	-60
68.50	Old Emigrant road N.W.	
80.05	Cor. to secs. 15, 16, 21 & 22. Land, rolling hills. Soil, 2nd rate, rocky. Grass, good.	
North bet. secs. 15 & 16.		
	Var. 19° East.	
16.00	Old Emigrant road N.W.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of stone & earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.	
40.00	Set basalt stone 18 x 9 x 8 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face and raise mound of stone over it. Pits impracticable.	
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stone, 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.	
80.00	Set basalt stone 18 x 12 x 8 ins., 12 ins. in the ground for cor. to secs. 9, 10, 15 & 16, marked with 4 notches on S. and 3 notches on E. edges; dug pits 18 x 18 x 12 ins. in each sec. 5 $\frac{1}{2}$ ft. dist. and raised mound of earth	