

Subdivisions, T. 2 N., R. 34 E.

Chains		
	N. 89° 39' W. on true line. Var. 20° East	
19.94	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E. & W. of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.	
26.50	Gulch, N.	-50
39.88	Deposited charred stake 12 ins. in the ground for ¼ sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake, 5½ ft. dist. and raised mound of stone & earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.	
41.50	Wagon road N.	
59.82	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of cor. 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.	
68.50	Gulch, N.	-10
79.75	Cor. to secs. 3, 4, 9 & 10. Land, rolling and hilly. Soil, 1st rate. Grass, good. Well adapted to agriculture. No timber or water.	
	North bet. secs. 3 and 4. Var. 19½° East.	
2.20	Umatilla river, 150 lks. wide W.	
10.00	Leave river bottom.	
12.50	O.R. & N. Co. R.R., E & W.	
	Cayuse Station bears W. 2.40 chs.	
40.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for ¼ sec. corner, marked ¼ S on W. face; dug pits	