

Subdivisions, T. 2 N., R. 34 E.

Chains		
	East on random bet. secs. 21 and 28.	
	Var. 20° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.30	Intersect N & S line 30 lks. S. of cor. to secs. 21, 22, 27 & 28.	
	Thence	
	S.89° 47' W. on true line.	
	Var. 21-3/4° East.	
12.00	Dry gulch N.	-400
39.65	Set basalt stone 14 x 10 x 8 ins., 10 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face; dug pits 18x18x12 ins. E. and W. of stone 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.	
	Begin ascent.	
50.00	Summit ridge N.	+500
	Descend.	
79.30	Cor. to secs. 20, 21, 28 & 29.	
	Land, rough and steep mountains 79.30 chs.	
	Soil, 4th rate. Some grass.	
	North bet. secs. 20 and 21.	
	Var. 20° East.	
17.00	Top ridge N.W.	+150
24.00	Gulch, N.W.	-100
27.50	Summit ridge N.W.	+100
32.00	Gulch, N.W.	-100
	Ascend.	
40.00	Set basalt stone 18 x 12 x 8 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face; raised mound of stone over it. Pits impracticable.	+100
47.00	Summit ridge W.	+250
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of cor. 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it. In N. pit drove stake, 2 ft. long, 2 ins.	