

Subdivisions, T. 2.N., R. 34 E.

Chains	
	for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face; raised mound of stone over it. Pits impracticable.
41.15	Wagon road N.E.
59.62	Set basalt stone 20 x 10 x 8 ins., 14 ins. in the ground for $\frac{1}{16}$ sec. cor.; marked $\frac{1}{16}$ on N. face; raised mound of stone over it. Pits impracticable.
78.50	Enter field.
79.50	Cor. to secs. 8, 9, 16 & 17. Land, rolling. Soil, 1st rate. Good grass.
	<hr/>
	North bet. secs. 8 and 9. Var. 21° 45' East
3.75	Leave field E & W.
18.50	Enter field E & W.
20.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. cor.; dug pits 18 x 18 x 12 ins. N. & S. of stake $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{16}$ S on W. face.
40.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on W face.
60.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{16}$ S on W. face.
76.25	Leave field E & W.
76.50	Wagon road E & W.
77.75	Bluff rock 25 ft. high E & W.
80.00	Set basalt stone 16 x 8 x 7 ins., 12 ins. in the ground